


SHIPPING, RIGGING, HOISTING AND ASSEMBLY MANUAL ENERGY RECOVERY VENTILATORS

LE6X LE8X LE10X











IMPORTANT SAFETY INFORMATION

WARNING

RISK OF DEATH OR SERIOUS INJURY

Hoisting heavy equipment overhead is inherently dangerous. Failure to properly rig the ERV for hoisting or the use of incorrect rigging equipment may result in the ERV falling during hoisting. Improper work procedures may result in death or serious injury to workers. Rigging, hoisting and assembly are to be performed by skilled and experienced personnel. OSHA-approved work guidelines are to be strictly followed.

Before proceeding with installation, read all instructions, verifying that all the parts are included.

The information in this manual is provided as a guideline and does not neccessarily meet all local codes. It is the installer's responsibility to comply with all local codes and OSHA-approved safety practices.

NOTICE

This unit is for ventilating finished structures only. It is not to be used until after all construction has been completed and construction debris and dust are cleaned from the Occupied Space.

NOTICE

Do not lift joined unit by the 4 corner lifting lugs only. Secure lifting cables to the center lifting lugs also.

All lifting lugs provided must be used. Never lift the unit or modules from the top of the unit.

Incorrect lifting can cause damage to the unit.

IMPORTANT

If this unit is installed in an area where it may draw air from a nearby fuel-burning device such as a gas furnace or water heater, verify that the air being extracted by the ERV does not conflict with proper operation of the fuel-burning device.

NOTICE

RISK OF DAMAGE TO ENTHALPIC CORES

Whenever working within the ERV cabinet, protect the enthalpic cores from accidental damage. The core media is subject to damage from dropped tools or other foreign objects.

NOTICE

RISK OF DAMAGE TO ERV CABINET

Incorrect lifting can cause damage to the unit.

Do not lift joined unit by the 4 corner lifting lugs only. Secure lifting cables to the center lifting lugs also.

All lifting lugs provided must be used. Never lift the unit or modules from the top of the unit.

NOTICE

This unit is intended for general ventilating only. Do not use to exhaust hazardous or explosive materials and vapors. Do not connect this equipment to range hoods, fume hoods or collection systems for toxics.

NOTICE

This equipment is to be installed by following Industry Best Practices and all applicable codes. Any damage to components, assemblies, subassemblies or the cabinet which is caused by improper installation practices will void the warranty.

IMPORTANT

This unit can be delivered in two modules for on-site assembly or as a completely assembled unit (additional charges apply). See separate unit-specific Installation, Operation and Maintenance manual for further information.



IMPORTANT USER INFORMATION

READ AND SAVE THIS MANUAL/LIRE ET CONSERVER CE MANUEL

UNIT INFORMATION

In the unlikely event that factory assistance is ever required, information located on the unit label will be needed.



Unit Label (typical)



TABLE OF CONTENTS

UNIT INFORMATION	3
1.0 SHIPPING 1.1 RECEIVING AND HANDLING 1.2 STORAGE BEFORE INSTALLATION	6 6 6
2.0 RIGGING 2.1 REQUIRED RIGGING EQUIPMENT	7 7
3.0 FORKLIFT REQUIREMENTS	9
4.0 MODULE ASSEMBLY 4.1 CONFIGURATION LABEL 4.2 ASSEMBLY PREPARATION	9 9
4.3 REMOVE SHIPPING STRAPS 4.4 APPLY FOAM GASKET TAPE 4.5 JOIN MODULES TOGETHER	10 10 11
4.5.1 Bolt Together at Lifting Lugs 4.5.2 Bolt Together Mating Roof Beams 4.5.3 Caulk The Seams	11 12 13
4.5.4 Install Joining Roof Cap 4.5.5 Install Assembly Straps	13 14
4.5.6 Install Roof End Joining Caps 4.6 CONNECT THE WIRING HARNESS 4.7 INSTALL WEATHERHOODS 4.8 INSTALL MERV-8 FILTERS	14 15 16
5.0 ROOFTOP CURB DIMENSIONS 5.1 LE6XRT CURBS 5.2 LE8XRT CURBS 5.3 LE10XRT CURBS	17 18 18 18
6.0 ROOFTOP UNIT DIMENSIONS 6.1 LE6XRTH-F DIMENSION DRAWING 6.2 LE6XRTV-R DIMENSION DRAWING 6.3 LE8XRTH-F DIMENSION DRAWING 6.4 LE8XRTV-R DIMENSION DRAWING 6.5 LE10XRTH-F DIMENSION DRAWING 6.6 LE10XRTV-R DIMENSION DRAWING	20 20 20 21 21 22 22
7.0 INDOOR UNIT DIMENSIONS 7.1 LE6XINH DIMENSION DRAWING 7.2 LE6XINV DIMENSION DRAWING 7.3 LE8XINH DIMENSION DRAWING 7.4 LE8XINV DIMENSION DRAWING 7.5 LE10XINH DIMENSION DRAWING 7.6 LE10XINV DIMENSION DRAWING	23 23 23 24 24 25 25
8.0 LE6X CORNER WEIGHTS 8.1 LE6XRT CORNER WEIGHTS 8.2 LE6XINH CORNER WEIGHTS 8.3 LE6XINVH CORNER WEIGHTS	26 26 27 27
9.0 LE8X CORNER WEIGHTS 9.1 LE8XRT CORNER WEIGHTS 9.2 LE8XINH CORNER WEIGHTS 9.3 LE8XINVH CORNER WEIGHTS	28 28 29 29
10.0 LE10X CORNER WEIGHTS 10.1 LE10XRT CORNER WEIGHTS 10.2 LE10XINH CORNER WEIGHTS 10.3 LE10XINVH CORNER WEIGHTS	30 30 31



TABLE OF ILLUSTRATIONS

Unit Label (typical)	3
LE ERV Hood Shipping Location (typ)	6
Rigging Assembly Graphic 1	8
Rigging Assembly Graphic 2	8
Corner Lifting Lug (typ)	8
Shipping Straps Location	10
Foam Gasketing Tape Location (typ)	10
Module Positioning Technique	11
LE Indoor Unit Base Bolt Locations	11
LE Rooftop Unit Base Bolt Locations	11
Alignment / Spacer Bolt Location	11
Roof Beam Assembly Graphic 2	12
Roof Beam Assembly Graphic 1	12
Roof Beam Assembly Bolt Locations	12
Roof Cap Caulking	13
Roof Beam Caulking	13
Assembly Strap Locations	14
Roof End Joining Caps	14
Assembly Strap Installation	14
Wiring Harness Access Panel	15
Wiring Harness Routing	15
Access Panel Removal	15
Wiring Harness Connections	15
OA Hood Screw Locations	16
EA Hood Screw Locations	16
Access Panel Installation	16
OA Hood Installation	16
EA Hood Installation	16
Filter Spacers	17
Filter Racks	17
Filter Extractor Hook	17



1.0 SHIPPING

All ERVs are palletized and then shipped by common carrier. It is the installer's / customer's responsibility to coordinate delivery and properly handle the shipment during unloading and storage.

1.1 RECEIVING AND HANDLING

Upon delivery of the ERV, inspect it carefully for shipping damage and completeness. Verify the presence of any accessories such as external hoods that are to be field-installed or filters that are shipped loose. If shipping damage is discovered, take digital pictures and note the visible damage on the shipping manifest. Notify your RenewAire dealer immediately.

Note that whenever possible, accessories such as weather hoods are assembled and then secured for shipping inside the ERV. See photo below.

Hoods are assembled at the factory and then secured for shipment inside the ERV.



LE ERV Hood Shipping Location (typ)

LE models can be delivered in two modules for on-site assembly or as a complete unit (additional charges apply).

In all cases, extra protective pallet materials may have been added; this material was added at the factory to protect the unit or modules during shipping.

In all cases, when shipped as modules, assembly materials ship loose and can be found inside the modules. Note that assembly materials must be removed and installed prior to unit operation.

For rooftop models, the outdoor air weather hoods ship loose and can be found inside the modules. Note that weather hoods and assembly materials must be removed and installed prior to unit operation.

1.2 STORAGE BEFORE INSTALLATION

If installation will not occur immediately following delivery, store equipment in a dry protected area away from construction traffic and in the proper orientation as marked on the packaging with all internal packaging in place.

When placing the ERV on the ground, the placement area should be flat and level. Take care to avoid twisting or wracking of the unit.



2.0 RIGGING

The unit comes equipped with base rail lifting lugs at the lower 4 corners and in the middle of the unit.

Each lifting lugs come equipped with a 2" diameter hole which will accommodate a 1.5" dia. schedule 40 steel pipe (not provided).

Unit or module sections shall be lifted by cables attached to all of the lifting lugs.

If cables or chains are used to lift the unit they must be the same length. Care should be taken not to damage the cabinet, dampers, or electrical box.

Adjustable spreader bars should be used to properly support the unit in order to properly distribute the load thus applying an even vertical lifting force to all of the lifting lugs. This will prevent structural damage to the unit.

Also adjustable spreader bars should be used to maintain the required 10" clearance between the cables and the cabinet or any of the equipment attached to the unit or modules.

Provide additional blocking or covering as required.

Secure hooks and cables at all lifting points.

Take up slack in cables gradually as to avoid sudden movements as this may cause the unit or modules to shift.

Suspending the unit or modules for an extended period of time is not recommended and it is advised to place the unit as soon as possible after lifting.

Do not lift in high winds.

RenewAire will not be responsible for any damage during the rigging, lifting or installing of the unit or modules.

Refer to Corner Weight Charts for exact center of gravity.


2.1 REQUIRED RIGGING EQUIPMENT

All rigging equipment is to be provided by the installing Contractor.


Rigging procedures may differ depending on the physical dimensions of the unit or modules, it's location, the job site, or Installing Contractor preferences.

Tools needed (Suggested):
Crane to lift proper capacity
Adjustable spreader bars
Cables
1.5" Dia. steel pipe schedule 40.
Tools to pull modules together, chains, bar clamps, come alongs etc.
Miscellaneous (SAE) wrenches and 1/2" drive socket wrenches with short extensions





Rigging Assembly Graphic 1



Rigging Assembly Graphic 2



Corner Lifting Lug (typ)



3.0 FORKLIFT REQUIREMENTS

When lifting individual modules, forklift extensions must be used and a minimum length of 72" (96" preferred).

When lifting modules off the pallets:

If entering from the door side or the open side of the module ensure forks extend in far enough as to catch the furthest away stringer with fork extensions.

If entering from the side of the module, insure forks extend all the way through the module.

NOTICE

Do not attempt to lift a rooftop module off the pallet from the door side or open side as there are no stringers under the unit to carry the load.

Assembled modules should never be lifted using a forklift.

4.0 MODULE ASSEMBLY

4.1 CONFIGURATION LABEL

RenewAire LE series Energy Recovery Ventilators can either be built and shipped factory assembled or be ordered unassembled for applications where modules must be manipulated separately. If the unit was ordered unassembled, then you will need to assemble the modules in the field.

Each module is labeled with a configuration and serial number label. Locate these labels and insure each module assembled together have the same configuration and serial number. See the image on page 3 of this manual.

If for any reason you are unable to identify a module or its position in the final assembly, then consult the Installation Contractor or RenewAire Customer Service.

4.2 ASSEMBLY PREPARATION

Extra protective pallet material has to be removed prior to assembly. This additional pallet material was added at the factory to protect the unit during shipping.

Also, plywood protective packaging material has to be removed from modules before assembly.


It is desirable to situate all required modules in the installation location as near as possible to the order in which they will be connected. Be sure to leave enough space to work between modules before connection. Gasket tape will be applied before assembling the modules.

All materials for assembling the modules are supplied by RenewAire.



4.3 REMOVE SHIPPING STRAPS

Remove shipping straps from opening/mating ends before joining modules and operating the unit. Shipping straps are attached to the modules at the factory. These straps insure proper rigidity when shipping and lifting. Once the straps are removed they may be disposed of along with the screws that held them in place.



Shipping Straps Location

4.4 APPLY FOAM GASKET TAPE

Apply 1/2" X 1" gasket tape (provided), as shown below. Gasket tape creates an airtight seal between modules. The adhesive backing on the gasket tape is easily repositioned during assembly if needed. However, if gasket tape is allowed to set more than 48 hours, it will be difficult to reposition.



INSTALL FOAM GASKETING TAPE AS SHOWN HERE. (Gasketing is shown in red for clarity)

NOTE: Failure to apply foam gasketing tape as shown here will compromise water and airtight seal of the unit.

Foam Gasketing Tape Location (typ)



4.5 JOIN MODULES TOGETHER

Align modules and push together using forklift or other means, compressing the gasket tape. The lower lifting lugs are equipped with 2" diameter holes that 1.5" dia. (2" OD) steel pipe could be used to assist in alignment. See Lifting Lug illustration on page 8 of this manual. Joining lift lugs also have a spacing bolt at the tip of one lug that will fit into the empty lug hole of the other module for alignment and lug tip spacing.



ALIGNMENT / SPACER BOLT




Alignment / Spacer Bolt Location

Module Positioning Technique

4.5.1 Bolt Together at Lifting Lugs

After positioning the modules together, compressing the gasket tape, insert eight 3/8" - $16 \times 1-1/4$ plated hex head bolts through the holes on the lifting lugs and base rail (LE-IN) or base supports (LE-RT) of the two adjacent modules. Use 3/8" washers between the bolt head and the unit and between the nut and the unit. Fasten the nuts to the bolts secure the bases of the two modules together tightly.




LE Indoor Unit Base Bolt Locations

LE INDOOR UNITS:

INSTALL 2 BOLTS IN THE MATING LIFT-ING LUGS AND THEN 2 MORE BOLTS IN THE MATING BASE RAILS. TYPICAL EACH SIDE OF LE UNIT.

2 BOLTS THROUGH BASE RAILS (EACH SIDE OF UNIT). ACCESS BOLT AND NUT THROUGH THE HAND HOLES IN EACH MODULE SIDE BASE RAIL TO BE JOINED.

2 BOLTS THROUGH BASE SUP-PORTS (EACH SIDE OF UNIT). ACCESS BOLT AND NUT THROUGH HAND HOLES IN EACH MODULE SIDE BASE RAIL TO BE JOINED.



LE Rooftop Unit Base Bolt Locations

LE ROOFTOP UNITS:

INSTALL 2 BOLTS IN THE MATING LIFTING LUGS AND THEN 2 MORE BOLTS IN BASE SUPPORT.

2 BOLTS THROUGH LIFTING LUGS (EACH SIDE OF UNIT)



4.5.2 Bolt Together Mating Roof Beams

Use bar clamps, or other non-destructive winching device to pull the top of the modules together tightly compressing the gasket. After aligning the 4 roof bolt locations, insert 1/4" - 20 x 1.00" Grade 5 zinc plated hex head bolts through the holes in the roof beam. Secure the nuts to secure the roof section.




AFTER THE LIFTING LUG AS-SEMBLIES HAVE BEEN BOLTED TOGETHER, RAISE ONE END OF THE UNIT TO COMPRESS THE GASKETING AND BRING BOTH OF THE MATING ROOF BEAMS INTO TIGHT CONTACT.

Roof Beam Assembly Graphic 1



USE A PIPE CLAMP TO ADJUST THE ROOF BEAMS LATERALLY AND THEN BOLT TOGETHER THE TWO ROOF BEAMS.

Roof Beam Assembly Graphic 2




Roof Beam Assembly Bolt Locations



4.5.3 Caulk The Seams

Attention should be taken to assure the modules are forming an air and water tight seal.

Apply a continuous ½" bead of Tremsil 600 Silicone Sealant caulk (provided) at the seam along the entire roof and sides of the unit.




NOTE: Failure to apply caulk in these locations will compromise the water and airtight seal of the unit.

Roof Beam Caulking

4.5.4 Install Joining Roof Cap

A galvanized cap roof flange is provided to seal the roof seam and to maintain a water and airtight seal. The cap roof flange is provided with pre-drilled holes. #12 X .75 hex head tek screw w/washers are provided to attach the cap roof flange.

For best results, use a lower torque setting on the power drill. Be careful not to over tighten the screw.



NOTE: Failure to install the roof cap will compromise the water and airtight integrity of the unit.


Roof Cap Caulking



4.5.5 Install Assembly Straps

Two (2) galvanized metal assembly straps are used to secure the module seams to assist in maintaining a water and airtight seal and provide structural rigidity during lifting. One (1) used on each side of the unit. These straps are provided with pre-drilled holes. #12 X 3/4" hex head tek screw w/washers are provided to attach the joining straps to the unit. For additional protection, caulk sides of straps after attachment.

For best results, use a lower torque setting on the power drill. Be careful not to over tighten the screw.





Assembly Strap Locations


Assembly Strap Installation



NOTE: Failure to install the assembly straps will compromise the structural integrity of the unit and cause damage during lifting. It will also compromise the water and airtight integrity of the unit.

4.5.6 Install Roof End Joining Caps

Two (2) galvanized roof cap ends are provided to seal the top end of each module and maintain a water and airtight seal. The roof cap joining ends are provided with pre-drilled holes. #12 X 3/4" hex head tek screw w/washers are provided to attach these roof cap joining ends to the unit.



Roof End Joining Caps



NOTE: Failure to install roof cap ends will compromise the structural integrity of the unit and cause unit damage during lifting. It will also compromise the water and airtight integrity of the unit.





4.6 CONNECT THE WIRING HARNESS

Internal wiring connections are required after modules are fastened together, and before connection of unit supply power. For INH and RT models, the back module comes pre-wired with the exhaust air blower wires being routed from the motor to the open end of the module. The wiring harnesses end in plugs, ready for connection.

If the back module is equipped with isolation dampers, they are also pre-wired with the damper wires being routed from the damper actuators to the open end of the module. The ends of the damper wiring harnesses also end in plugs, ready for connection.

After the modules are joined together, open the electrical connection cover on the E-Box side of the front module by removing screws in the access panel. The access panel is located in the upper left corner of the front module, to the left of the E-Box.






Wiring Harness Access Panel

Access Panel Removal

Inside the access panel are low voltage and high voltage wiring connection compartments. The low voltage compartment is the lower compartment and the high voltage compartment is the upper compartment. Both compartments are open on the left side to access the wiring harness plugs that are coming from the exhaust air blower and isolation dampers (if equipped).




Wiring Harness Routing

Wiring Harness Connections

Reach through the open left side of the compartments and into the rear module. Guide the wiring harness(es) into the wiring connection compartments in the front module. Plug each wiring harness into its matching connector, located in the wiring connection compartments. Secure excess wire with wire ties.



Replace the access cover by sliding the top edge of the cover behind the edge of the roof pan and replace the screws. Caulk the sides and bottom of the access panel with factory-supplied caulk.




Access Panel Installation


4.7 INSTALL WEATHERHOODS

Rooftop units (RT models) have weatherhoods that are shipped loose and must be field-installed. Installation of the hoods is normally performed after all rigging and hoisting is completed because of the chance of damage to the hoods by the rigging equipment.

All weatherhoods have a flange on the top rear that must be inserted behind the roof panel overhang. To install any hood, remove the factory-installed roof edge screws and keep them for re-use. OUTSIDE AIR HOODS




OA Hood Screw Locations




OA Hood Installation

Slide the top flange of the OA air hood beneath the roof panel overhang. Reinstall the screws in the roof edge and then install screws along the sides and lower edge of each hood.

EXHAUST AIR HOODS



EA Hood Screw Locations



EA Hood Installation

Slide the top flange of the EA air hood beneath the roof panel overhang. Reinstall the screws in the roof edge and then install screws along the sides and lower edge of each hood.




4.8 INSTALL MERV-8 FILTERS

LE units ship with 20" X 25" X 2" (nominal) MERV-8 air filters. Filters are shipped loose in LE-RT units or may be installed prior to shipment in LE-IN units. In addition, RenewAire provides a set of filter spacers and a filter extractor hook, all shipped loose.


The filter spacers have a tab on the ends where a pull cord can be inserted. With a cord installed in the tab holes, it is possible to to simply pull the cords and withdraw all the filters in a filter bank at once. See image below. When installing the filter spacers, the foam strip is to be placed against the filter.

Note that when filters are installed, the filter spacers may tend to fall off the end of the filter receiving channels. If this happens, simply install the spacers between the first two filters in from the door., instead of locating them against the access doors.

Install filters in filter racks with airflow direction arrow on filters correctly oriented. The short sides of the filter will slide in the filter channels.



RenewAire recommends that the factory-provided MERV-8 filters be installed immediately and be kept in place during the construction and installation phases. Once the unit is fully installed, the filters may be changed to the desired efficiency and thickness. See the unit-specific manual for filter changing options and procedures.




Filter Racks




5.0 ROOFTOP CURB DIMENSIONS

5.1 LE6XRT CURBS

NOTE: See Curb Clip
Installation Manual
and Curb Clips Design
Notes document for
LE-RT suggested installation
instructions on a rooftop
curb.





5.2 LE8XRT CURBS





5.3 LE10XRT CURBS









6.0 ROOFTOP UNIT DIMENSIONS


6.1 LE6XRTH-F DIMENSION DRAWING




6.2 LE6XRTV-R DIMENSION DRAWING



6.3 LE8XRTH-F DIMENSION DRAWING




6.4 LE8XRTV-R DIMENSION DRAWING






6.5 LE10XRTH-F DIMENSION DRAWING




6.6 LE10XRTV-R DIMENSION DRAWING






7.0 INDOOR UNIT DIMENSIONS

7.1 LE6XINH DIMENSION DRAWING




7.2 LE6XINV DIMENSION DRAWING






7.3 LE8XINH DIMENSION DRAWING




7.4 LE8XINV DIMENSION DRAWING






7.5 LE10XINH DIMENSION DRAWING



7.6 LE10XINV DIMENSION DRAWING





8.0 LE6X CORNER WEIGHTS

73.5" Lifting Lug LR RR B" RF RF


8.1 LE6XRT CORNER WEIGHTS

BAS	IC UNIT	WEIGH	ITS (lbs.)	
Motors	UNIT	LF	LR	RR	RF
3 HP	2086	579	580	464	463
5 HP	2100	583	585	466	465
7.5 HP	2218	625	630	483	480
ADDITIONAL	WEIGH	ITS FOR	ROPTIC	NS (lbs	.)
Options	UNIT	LF	LR	RR	RF
Double Wall	418	105	104	104	105
VFDs	12	10	1	0	1
RA or EA Damper	47	11	1	10	25
OA or FA Damper	58	2	2	27	27
Total Selected Weights					
Add the additional weights	for option	s to the Ba	sic Unit we	iahts deter	mined by

Add the additional weights for options to the Basic Unit weights determined by motor size to determine Unit and Corner weights for a specific unit.

Corner weights shown above include weatherhoods INSIDE THE UNIT, as shipped.

Center of gravity: A=32" B=61" (+/- 2")




BASIC	MODUL	E WEIG	SHTS (Ib	s.)	
Motors	UNIT	LF	LR	RR	RF
3 HP	1017	252	190	247	328
5 HP	1024	253	190	249	332
7.5 HP	1083	268	190	260	365
ADDITIONAL	WEIGH	ITS FOR	ROPTIC	NS (lbs	.)
Options	UNIT	LF	LR	RR	RF
Double Wall	209	64	40	40	64
VFDs	0	0	0	0	0
RA or EA Damper	0	0	0	0	0
OA or FA Damper	58	2	2	27	27
Total Selected Weights					

motor size to determine Unit and Corner weights for a specific unit.

Corner weights shown above include weatherhoods INSIDE THE UNIT, as shipped.

Center of gravity: A=42" B=25" (+/- 2")



BASIC	MODUI	E WEI	SHTS (Ib	s.)	
Motors	UNIT	LF	LR	RR	RF
3 HP	1068	281	243	253	292
5 HP	1076	283	245	254	294
7.5 HP	1135	308	258	259	309
ADDITIONAL	WEIGH	ITS FOR	ROPTIC	NS (lbs	.)
Options	UNIT	LF	LR	RR	RF
Double Wall	209	64	40	40	64
VFDs	12	10	1	0	1
RA or EA Damper	47	11	1	10	25
OA or FA Damper	58	2	2	27	27
Total Selected Weights					

Add the additional weights for options to the Basic Unit weights determined by motor size to determine Unit and Corner weights for a specific unit. Corner weights shown above include weatherhoods INSIDE THE UNIT, as shipped.

Center of gravity: A=37" B=27" (+/- 2")



8.2 LE6XINH CORNER WEIGHTS

IC UNIT	WEIGH	TS (lbs.)	
UNIT	LF	LR	RR	RF
1975	565	550	424	436
1989	570	555	426	438
2106	611	600	443	452
WEIGH	HTS FOR	ROPTIC	NS (lbs	.)
UNIT	LF	LR	RR	RF
418	105	104	104	105
12	10	1	0	1
47	3	1	14	29
47	1	3	29	1
	UNIT 1975 1989 2106 . WEIGH UNIT 418 12 47	UNIT LF 1975 565 1989 570 2106 611 WEIGHTS FOR UNIT LF 418 105 12 10 47 3	UNIT LF LR 1975 565 550 1989 570 555 2106 611 600 WEIGHTS FOR OPTIC UNIT LF LR 418 105 104 12 10 1 47 3 1	1975 565 550 424 1989 570 555 426 2106 611 600 443 WEIGHTS FOR OPTIONS (Ibs. UNIT LF LR RR 418 105 104 104 12 10 1 0 47 3 1 14

Add the additional weights for options to the Basic Unit weights determined by motor size to determine Unit and Corner weights for a specific unit.

Center of gravity: A=32" B=61" (+/- 2")

BASIC	MODUI	E WEIG	SHTS (IL	s.)	
Motors	UNIT	LF	LR	RR	RF
3 HP	943	229	174	233	306
5 HP	950	230	174	235	310
7.5 HP	1009	245	175	246	343
ADDITIONAL	WEIGH	ITS FOR	ROPTIC	NS (lbs	.)
Options	UNIT	LF	LR	RR	RF
Double Wall	209	64	40	40	64
VFDs	0	0	0	0	0
RA or EA Damper	0	0	0	0	0
OA or FA Damper	47	1	3	29	14
Total Selected Weights					
Add the additional weights motor size to determine U					mined by

BASIC	MODUI	_E WEIC	GHTS (lb	 s.)	
Motors	UNIT	LF	LR	RR	RF
3 HP	1032	307	261	213	250
5 HP	1039	310	263	214	252
7.5 HP	1099	338	277	218	266
ADDITIONAL	WEIGH	ITS FOF	R OPTIC	NS (lbs.	.)
Options	UNIT	LF	LR	RR	RF
Double Wall	209	64	40	40	64
VFDs	12	10	1	0	1
RA or EA Damper	47	3	1	14	29
OA or FA Damper	0	0	0	0	0
Total Selected Weights					
Add the additional weights motor size to determine U				•	mined by
Center of gravity: A=33" B			s Ibi a spec	alle unit.	

8.3 LE6XINV CORNER WEIGHTS

BAS	IC UNIT	WEIGH	ITS (lbs.)	
Motors	UNIT	LF	LR	RR	RF
3 HP	1984	569	433	424	558
5 HP	1998	575	434	425	563
7.5 HP	2116	626	442	434	614
ADDITIONAL	WEIGH	ITS FOR	ROPTIC	NS (lbs.	.)
Motors	UNIT	LF	LR	RR	RF
Double Wall	418	105	104	104	105
VFDs	12	10	1	0	1
RA or EA Damper	47	14	29	3	1
OA or FA Damper	47	1	3	29	14
Total Selected Weights					
Add the additional weight	s for option	s to the Ba	sic Unit we	ights deter	mined by

Add the additional weights for options to the Basic Unit weights determined by motor size to determine Unit and Corner weights for a specific unit.

Center of gravity: A=32" B=57" (+/- 2")


BASIC	MODUL	_E WEIC	GHTS (lb	os.)	
Motors	UNIT	LF	LR	RR	RF
3 HP					
5 HP	715	207	158	151	198
7.5 HP					
ADDITIONAL	WEIGH	ITS FOF	ROPTIC	NS (lbs.	.)
Options	UNIT	LF	LR	RR	RF
Double Wall	209	64	40	40	64
VFDs	0	0	0	0	0
RA or EA Damper	47	14	29	3	1
OA or FA Damper	47	1	3	29	14
Total Selected Weights					
Add the additional weights motor size to determine U					nined by
Center of gravity: A=36" B	=23" (+/- 2"	.")			

BASIC	MODUL	_E WEIC	GHTS (lb	os.)		
Motors	UNIT	LF	LR	RR	RF	
3 HP	1269	341	304	294	330	
5 HP	1283	345	306	297	335	
7.5 HP	1401	387	323	314	376	
ADDITIONAL	ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)					
Options	UNIT	LF	LR	RR	RF	
Double Wall	209	64	40	40	64	
VFDs	12	10	3	0	1	
RA or EA Damper	0	0	0	0	0	
OA or FA Damper	0	0	0	0	0	
Total Selected Weights						
Add the additional weights motor size to determine U					mined by	
Center of gravity: A=36" B	=27" (+/- 2	")				




Center of gravity: A=42" B=25" (+/- 2")

9.0 LE8X CORNER WEIGHTS




9.1 LE8XRT CORNER WEIGHTS

Motors	UNIT	LF	LR	RR	RF
3 HP	2625	753	680	568	624
5 HP	2645	745	737	578	585
7.5 HP	2763	790	780	593	600
ADDITIONAL	WEIGH	ITS FOR	ROPTIC	NS (lbs	.)
Options	UNIT	LF	LR	RR	RF
Double Wall	524	131	131	131	131
VFDs	12	10	1	0	1
RA or EA Damper	66	14	1	12	39
OA or FA Damper	88	2	2	42	42
Total Selected Weights					
Add the additional weights motor size to determine U					mined b



	UNIT	LF	LR	RR	RF				
3 HP	1320	322	244	325	429				
5 HP	1327	323	244	327	433				
7.5 HP	1386	330	248	347	460				
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)									
Options	UNIT	LF	LR	RR	RF				
Double Wall	263	78	54	54	78				
VFDs	0	0	0	0	0				
RA or EA Damper	0	0	0	0	0				
OA or FA Damper	88	2	2	42	42				
otal Selected Weights									



2, 10.10	MODUL			,				
Motors	UNIT	LF	LR	RR	RF			
3 HP	1311	412	301	252	346			
5 HP	1318	416	302	252	348			
7.5 HP	1377	448	313	253	363			
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)								
Motors	UNIT	LF	LR	RR	RF			
Double Wall	263	78	53	53	78			
VFDs	12	10	1	0	1			
RA or EA Damper	66	14	1	12	39			
OA or FA Damper	88	2	2	42	42			
Total Selected Weights								

Corner weights shown above include weatherhoods INSIDE THE UNIT, as shipped.

Center of gravity: A=33" B=33" (+/- 2")

Center of gravity: A=33" B=32-3/4" (+/- 2")



9.2 LE8XINH CORNER WEIGHTS

BASIC UNIT WEIGHTS (lbs.)										
Motors	UNIT	LF	LR	RR	RF					
3 HP	2480	732	637	517	594					
5 HP	2493	724	693	526	550					
7.5 HP	2611	769	737	541	564					
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)										
Options	UNIT	LF	LR	RR	RF					
Double Wall	524	131	131	131	131					
VFDs	12	10	1	0	1					
RA or EA Damper	66	3	1	20	42					
OA or FA Damper	66	1	3	42	20					
Total Selected Weights										
Add the additional weights motor size to determine U					mined by					

Center of gravity: A=32" B=80" (+/- 2")

BASIC UNIT WEIGHTS (lbs.)									
Motors	UNIT	LF	LR	RR	RF				
3 HP	1214	286	229	311	388				
5 HP	1221	288	229	312	393				
7.5 HP	1280	301	228	324	428				
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)									
Options	UNIT	LF	LR	RR	RF				
Double Wall	263	78	54	54	78				
VFDs	0	0	0	0	0				
RA or EA Damper	0	0	0	0	0				
OA or FA Damper	66	1	3	42	20				
Total Selected Weights									

Add the additional weights for options to the Basic Module weights determined by motor size to determine Module and Corner weights for a specific unit.

Center of gravity: A=37* B=35* (+/- 2*)

BASIC MODULE WEIGHTS (lbs.)								
Motors	UNIT	LF	LR	RR	RF			
3 HP	1265	409	295	235	326			
5 HP	1272	413	296	235	328			
7.5 HP	1331	445	307	236	343			
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)								
Options	UNIT	LF	LR	RR	RF			
Double Wall	263	78	54	54	78			
VFDs	12	10	1	0	1			
RA or EA Damper	66	3	1	20	42			
OA or FA Damper	0	0	0	0	0			
Total Selected Weights								

9.3 LE8XINV CORNER WEIGHTS

BAS	IC UNIT	WEIGH	IS (lbs.)			
Motors	UNIT	LF	LR	RR	RF		
3 HP	2495	727	524	521	723		
5 HP	2509	733	524	522	730		
7.5 HP	2627	787	530	527	783		
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)							
Options	UNIT	LF	LR	RR	RF		
Double Wall	524	131	131	131	131		
VFDs	12	10	1	0	1		
RA or EA Damper	66	20	42	3	1		
OA or FA Damper	66	1	3	42	20		
Total Selected Weights							

Add the additional weights for options to the Basic Unit weights determined by motor size to determine Unit and Corner weights for a specific unit.

Center of gravity: A=32" B=75" (+/- 2")

BAS	BASIC UNIT WEIGHTS (lbs.)									
Motors	UNIT	LF	LR	RR	RF					
3 HP										
5 HP	918	255	205	204	254					
7.5 HP										
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)										
Options	UNIT	LF	LR	RR	RF					
Double Wall	263	77	54	54	77					
VFDs	0	0	0	0	0					
RA or EA Damper	66	20	42	3	1					
OA or FA Damper	66	1	3	42	20					
Total Selected Weights										
A										

Add the additional weights for options to the Basic Module weights determined by motor size to determine Module and Corner weights for a specific unit.

Center of gravity: A=36-3/4" B=35" (+/- 2")

BASIC MODULE WEIGHTS (lbs.)									
Motors	UNIT	LF	LR	RR	RF				
3 HP	1577	461	329	328	459				
5 HP	1591	468	329	328	466				
7.5 HP	1709	515	341	339	513				
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)									
Options	UNIT	LF	LR	RR	RF				
Double Wall	263	78	53	53	78				
VFDs	12	10	1	0	1				
RA or EA Damper	0	0	0	0	0				
OA or FA Damper	0	0	0	0	0				
Total Selected Weights									
Add the additional weights	for ontion	s to the Ra	sic Module	weights de	termined				

Add the additional weights for options to the Basic Module weights determined by motor size to determine Module and Corner weights for a specific unit. Center of gravity: A=36" B=33" (+/- 2")




Center of gravity: A=33" B=33" (+/- 2")


10.0 LE10X CORNER WEIGHTS

10.1 LE10XRT CORNER WEIGHTS

Motors	UNIT	LF	LR	RR	RF			
3 HP	3031	842	841	674	674			
5 HP	3045	847	846	676	676			
7.5 HP	3163	892	890	690	691			
10 HP	3201	906	904	695	696			
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)								
Options	UNIT	LF	LR	RR	RF			
Double Wall	626	155	158	158	155			
VFDs	12	10	1	0	1			
RA or EA Damper	66	14	1	12	39			
OA or FA Damper	88	2	2	42	42			
Total Selected Weights								



Motors	UNIT	LF	LR	RR	RF			
3 HP	1539	330	334	440	435			
5 HP	1546	354	346	419	427			
7.5 HP	1605	363	348	437	456			
10 HP	1624	367	349	443	466			
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)								
Options	UNIT	LF	LR	RR	RF			
Double Wall	313	91	66	66	91			
VFDs	0	0	0	0	0			
RA or EA Damper	0	0	0	0	0			
OA or FA Damper	88	2	2	42	42			
Total Selected Weights								



Motors	UNIT	LF	LR	RR	RF			
3 HP	1493	445	396	307	344			
5 HP	1500	448	398	308	346			
7.5 HP	1559	474	415	313	357			
10 HP	1578	483	420	314	361			
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)								
Options	UNIT	LF	LR	RR	RF			
Double Wall	313	77	79	79	77			
VFDs	12	10	1	0	1			
RA or EA Damper	66	14	1	12	39			
OA or FA Damper	88	2	2	42	42			
Total Selected Weights								



10.2 LE10XINH CORNER WEIGHTS

BAS	BASIC UNIT WEIGHTS (lbs.)								
Motors	UNIT	LF	LR	RR	RF				
3 HP	2859	837	827	594	601				
5 HP	2872	842	832	595	603				
7.5 HP	2991	888	877	609	617				
10 HP	3028	902	891	614	621				
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)									
Options	UNIT	LF	LR	RR	RF				
Double Wall	627	156	159	158	154				
VFDs	12	10	1	0	1				
RA or EA Damper	66	3	1	20	42				
OA or FA Damper	66	1	3	0	1				
Total Selected Weights									
Add the additional weights motor size to determine U	nit and Cor	ner weight			mined by				

Center of gravity: A=32" B= 101" (+/- 2")

BAS	IC UNIT	WEIGH	ITS (lbs.)		
Motors	UNIT	LF	LR	RR	RF	
3 HP	1423	340	267	359	456	
5 HP	1430	341	268	361	460	
7.5 HP	1489	350	271	378	490	
10 HP	1508	353	271	384	499	
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)						
Options	UNIT	LF	LR	RR	RF	
Double Wall	313	91	66	66	91	
VFDs	0	0	0	0	0	
RA or EA Damper	0	0	0	0	0	
OA or FA Damper	66	1	3	42	20	
Total Selected Weights						
Add the additional weights motor size to determine U					mined by	
Center of gravity: A=43" [3=43" (+/- 2	2")				

BASIC UNIT WEIGHTS (lbs.)						
Motors	UNIT	LF	LR	RR	RF	
3 HP	1436	384	389	286	322	
5 HP	1443	441	391	287	323	
7.5 HP	1502	467	408	292	334	
10 HP	1521	477	412	293	339	
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)						
Options	UNIT	LF	LR	RR	RF	
Double Wall	313	78	79	79	78	
VFDs	12	10	1	0	1	
RA or EA Damper	66	14	1	12	39	
OA or FA Damper	0	0	0	0	0	
Total Selected Weights						
Add the additional weights motor size to determine U					mined by	

10.3 LE10XINV CORNER WEIGHTS

Motors	UNIT	LF	LR	RR	RF
3 HP	2859	819	665	616	759
5 HP	2873	825	666	617	765
7.5 HP	2990	874	676	628	812
10 HP	3028	889	679	632	828
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)					
Options	UNIT	LF	LR	RR	RF
Double Wall	616	153	155	155	153
VFDs	12	10	1	0	1
RA or EA Damper	66	20	42	3	1
OA or FA Damper	66	1	3	42	20
Total Selected Weights					

BASIC UNIT WEIGHTS (lbs.)						
Motors	UNIT	LF	LR	RR	RF	
3 HP	1127	349	204	212	362	
5 HP	1127	349	204	212	362	
7.5 HP	1127	349	204	212	362	
10 HP	1127	349	204	212	362	
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)						
Options	UNIT	LF	LR	RR	RF	
Double Wall	313	91	66	66	91	
VFDs	0	0	0	0	0	
RA or EA Damper	66	20	42	3	1	
OA or FA Damper	66	1	3	42	20	
Total Selected Weights						
Add the additional weights for options to the Basic Unit weights determined by motor size to determine Unit and Corner weights for a specific unit.						
Center of gravity: A=37" B= 37" (+/- 2")						

BASIC UNIT WEIGHTS (lbs.)					
Motors	UNIT	LF	LR	RR	RF
3 HP	1732	468	442	399	423
5 HP	1746	473	443	401	428
7.5 HP	1864	511	464	423	466
10 HP	1902	525	469	428	479
ADDITIONAL WEIGHTS FOR OPTIONS (lbs.)					
Options	UNIT	LF	LR	RR	RF
Double Wall	308	76	78	78	76
VFDs	12	10	1	0	1
RA or EA Damper	0	0	0	0	0
OA or FA Damper	0	0	0	0	0
Total Selected Weights					

Center of gravity: A=35" B= 47" (+/- 2")





ABOUT RENEWAIRE

For over 30 years, RenewAire has been a pioneer in enhancing indoor air quality (IAQ) in commercial and residential buildings of every size. This is achieved while maximizing sustainability through our fifth-generation, static-plate, enthalpic-core Energy Recovery Ventilators (ERVs) that optimize energy efficiency, lower capital costs via load reduction and decrease operational expenses by minimizing equipment needs, resulting in significant energy savings. Our ERVs are competitively priced, simple to install, easy to use and maintain and have a quick payback. They also enjoy the industry's best warranty with the lowest claims due to long-term reliability derived from innovative design practices, expert workmanship and Quick Response Manufacturing (QRM).

As the pioneer of static-plate core technology in North America, RenewAire is the largest ERV producer in the USA. We're committed to sustainable manufacturing and lessening our environmental footprint, and to that end our Waunakee, WI plant is 100% powered by wind turbines. The facility is also one of the few buildings worldwide to be LEED and Green Globes certified, as well as having achieved ENERGY STAR Building status. In 2010, RenewAire joined the Soler & Palau (S&P) Ventilation Group in order to provide direct access to the latest in energy-efficient air-moving technologies. For more information, visit: renewaire.com

USA

(800) 627-4499 FAX: (608) 221-2824 201 RAEMISCH ROAD WAUNAKEE, WISCONSIN 53597 USA WWW.RENEWAIRE.COM

CANADA

(905) 475-8989 FAX: (905) 475-5231 WWW.MITSUBISHIELECTRIC.CA

MEXICO,

CENTRAL &SOUTH AMERICA 52 (222) 2 233 911 FAX: 52 (222) 2 233 914 WWW.SOLER-PALAU.MX

